

SOUTHERLY CEPT: DESIGNING FOR INTERMITTENT USE

Columbus, Ohio One Water Conference

August 29, 2018

THE CITY OF COLUMBU ANDREW J. GINTHER MAYOR

DEPARTMENT OF PUBLIC UTILITIES







Challenges of Infrequent Use






What is CEPT?



- 110 MGD wet weather treatment train
- Partial treatment: removes
 TSS, BOD and disinfects
- Blended with WWTP effluent near outfall to meet NPDES permit
- Goal: Reduce CSOs & Eliminate SSOs

Designed for an average of 2 activations per year!



THROTTLING GATES 4 slide gates 78-inch mag meter

EFFLUENT LINE

96-in.
 Effluent
 Conduit

DISINFECTION CHAMBER

The Distance

- Chemical Induction Units
 CLARIE CEC
- 180' Diameter
- Sodium Hypochlorite Storage

- Sodium bisulfite
- Dry/wet weather

ARCADIS


Challenges of Infrequent Use

- Operational familiarity
- Complicated startup
- Shut down for long-term dormancy
- Maintaining mechanical readiness



Operational Familiarity


- Simplified SOPs workflows
- High level of automation requested
- Pre-programmed sequences to automate and guide through:
 - Startup
 - Shutdown
 - Flushing & draining
 - Equipment cycling
 - & others





Equipment Systems to Start Up

- Flow splitting slide gates
- Ferric chloride feed pumps
- Polymer blend units
- Clarifier sludge collector drives
- Primary sludge pumps
- Sodium Hypochlorite feed pumps & induction units
- Sodium Bisulfite feed pumps & induction units
- 3rd effluent flow meter
- Process monitoring instruments (pH and Turb)





General Startup Considerations

- Fill inf. conduit prior to throttling flow to CEPT: flood flow meter
- Chemical injection dose lead/lag times: proximity to storage and pumping
- Sequentially adjust throttling gates prior to increasing influent pumping
- Filling tanks and pump piping: evacuate trapped air





Startup Procedure

- Ready reserve influent pumping capacity
 - Bring an additional pump online
 - Maintain main plant < 330 MGD
 - Pumps prepared to ramp up when called upon
- Initiate Arm CEPT sequences
 - Carrier water for chemicals opens automatically
 - Drain valves close







GATE

CEPT Start: Flow Splitting

 Conduit fill gate floods influent line at 30 MGD to bring mag meter throttling gates online









CEPT Start: Chemical Feed

- Sequences initiate automatically:
 - Polymer
 - Ferric Chloride
 - Sodium Hypochlorite
 - Sodium Bisulfite
- Based on level, flow signals








CEPT Start: Clarifiers


- Operator prompted to start sludge collector drives when tanks are half full
- Sludge pumping sequence initiated manually
 - Pump allocation: (2X duty with standby)
 - Draw off rate(s)
 - Sludge destination
 - Grinders start automatically with pumps





Hibernation (Shutdown) Strategy

- Clear pumps and valves of process medias
- Flush sludge and chemical lines and leave full of water
- Drain clarifiers and conduits and leave drains open so rainwater does not collect.
- Reduce odors by clarifier washdown
- Keep stored polymer from stratifying
- Keep process monitoring instruments calibrated









Example: Primary Sludge Flush & Drain


































Maintaining Mechanical Readiness

- Strategy: Exercise pumps, valves, gates, collectors periodically using preprogrammed sequences
- Design allows for side stream cycling of clarification equipment during dry weather
 - Clarifiers are not filled
 - No discharge occurs
- Initiate CEPT Influent Cycling sequence followed by performing full shutdown SOP, including:
 - Flush, drain, and washdown sequences



ALL* moving equipment is exercised!





......

Chemical Feed Strategy

...........





Timing and Controls


- Disinfection Design Considerations
- Disinfection System Startup







CEPT Chemical Facilities



- CEPT Control Building
 - Ferric
 - Polymer
- Chlorine Control Building
 - Sodium Hypochlorite

Dechlorination Control Building

Sodium Bisulfite



Chemical Systems Start Up

Inputs


- Flows
- Levels at structures
- Gate/valve positions
- Process equipment readiness
- Monitoring/Sampling equipment readiness
- Systems interlock/permissive
- Chemical Feed Piping Lengths
 - Ferric
 - Polymer
 - Bisulfite
 - Hypochlorite





Disinfection










CEPT Disinfection Chamber




- Coordinated Effort
 - CEPT Clarifier Effluent
 - Vacuum Induction Units
 - CEPT Effluent Conduit





Disinfection










CEPT Dechlorination Structure










Flow and Chemical Adjustments





S88 and S89 'Fun' Facts:

Project documents:

- 623 total number of drawings
- 96 Instrumentation drawings
- 349 pages of functional requirements

Number of firms:

- Team of 14 Consulting Firms Schedule:
- Preliminary Design 2014 2015
- Design from 2015 2017
- Construction started June 2017





Under Construction







What's next ?

Operational Demonstration October 2019

- Initiate plant flow of 220 MGD or higher
- Weather Dependent
- Over a 6-month period
- Four successful demonstration events
- Simulated Flow Operational Demonstration ~ August 2019
 - Test field instruments
 - Programming
 - Personnel 'walk through'
 - Confirm SOP

Construction Closeout June 2020





Today's Speakers



SETH GRIMES Project Designer, Arcadis

O 614 985 9214

E seth.grimes@arcadis.com



VUI CHUNG

Project Manager, B&N

- O 614 459 2050 x 1243
- E vui.chung@burgessniple.com